



SITE TECH SOLUTIONS

3316 NE Sugarhill Ave #102B
Jensen Beach, FL 34957

Ph: 772-225-0909
sitetech@bellsouth.net

Job: SAMPLE (3)

AREA & VOLUME REPORT / 0-0-07

EXISTING vs DESIGN SUBGRADE

REPORT AREAS			IN-PLACE VOLUMES		ADJUSTED VOLUMES		
PARCEL ID	S/Y	ACRES	CUT	FILL	% LOSS	FILL	NET
BLDGPAD / 1	8,049	1.65	311	57	30%	74	237
BLDGPAD / 2	276	0.06	0	342	30%	445	(445)
BLDGPAD / 3	21	0.00	0	15	30%	20	(20)
BLDGPAD TOTAL:	8,346	1.71	311	414		539	(228)
		0.00					
EXCLISLAND / 1	1,048	0.22	0	660	30%	858	(858)
EXCLISLAND / 2	35	0.01	0	41	30%	53	(53)
EXCLISLAND / 3	481	0.10	1	142	30%	185	(184)
EXCLISLAND / 4	879	0.18	3	239	30%	311	(308)
EXCLISLAND / 5	563	0.12	0	357	30%	464	(464)
EXCLISLAND / 6	447	0.09	61	83	30%	108	(47)
EXCLISLAND TOTAL	3,452	0.71	65	1,522		1,979	(1,914)
		0.00					
HD - PAVE / 1	5,233	1.07	580	1,998	30%	2,597	(2,017)
HD - PAVE / 2	4,377	0.90	665	1,070	30%	1,391	(726)
HD TOTAL:	9,610	1.97	1,245	3,068		3,988	(2,743)
		0.00					
HDSW / 1	828	0.17	14	573	30%	745	(731)
HDSW / 2	1,048	0.22	184	123	30%	160	24
HDSW / 3	392	0.08	17	115	30%	150	(133)
HDSW TOTAL:	2,269	0.47	215	811		1,055	(840)
		0.00					
LD - PAVE / 1	1,866	0.38	30	193	30%	251	(221)
LD - PAVE / 2	2,709	0.56	760	55	30%	72	688
LD TOTAL:	4,575	0.94	790	248		323	467
		0.00					
PLAYCOURT / 1	561	0.12	18	419	30%	545	(527)
PLAYCOURT / 2	882	0.18	18	574	30%	746	(728)
PLAYCOURT TOTAL:	1,443	0.30	36	993		1,291	(1,255)
		0.00					
S/WSITE / 1	158	0.03	0	138	30%	179	(179)
S/WSITE / 2	46	0.01	3	0	30%	0	3
S/WSITE / 3	402	0.08	41	0	30%	0	41
S/WSITE / 4	25	0.01	9	0	30%	0	9
S/WSITE / 5	46	0.01	2	5	30%	7	(5)
S/WSITE / 6	178	0.04	10	15	30%	20	(10)
S/WSITE / 7	146	0.03	6	1	30%	1	5
S/WSITE / 8	205	0.04	0	245	30%	319	(319)
S/WSITE TOTAL:	1,205	0.25	71	404		526	(455)

REGIONS TOTAL	30,899	6.34	2,733	7,460		9,701	(6,968)
		0.00					
UNSPECIFIED	46,143	9.47	234	26,131	30%	33,970	(33,736)
JOB TOTAL	77,042	15.81	2,967	33,591		43,671	(40,704)
	S/Y	ACRES	C/Y CUT	C/Y FILL	COMP. LOSS	REQ. FILL	NET
	SURFACE AREA		IN-PLACE		w COMPACTION LOSS		

STRIP VOLUMES AND CONSTRUCTION MATERIALS							
SECTIONAL QTY'S	Plane Area			Slope Area		DEPTH	VOLUME
	S/F	S/Y	AC	S/F	S/Y		
BLDGPAD / 1	72,441	8,049	1.65	72,568	8,063	0.50	1,344
BLDGPAD / 2	2,480	276	0.06	2,496	277	0.50	46
BLDGPAD / 3	193	21	0.00	198	22	0.50	4
BLDGPADTOTAL:	75,114	8,346	1.71	75,262	8,362		1,394
			0.00				
EXCLISLAND / 1	9,433	1,048	0.22	9,535	1,059	0.00	0
EXCLISLAND / 2	313	35	0.01	328	36	0.00	0
EXCLISLAND / 3	4,328	481	0.10	4,394	488	0.00	0
EXCLISLAND / 4	7,910	879	0.18	8,006	890	0.00	0
EXCLISLAND / 5	5,063	563	0.12	5,212	579	0.00	0
EXCLISLAND / 6	4,020	447	0.09	4,149	461	0.00	0
EXCLISLAND TOTA	31,067	3,452	0.71	31,624	3,514		0
			0.00				
HD - PAVE / 1	47,100	5,233	1.07	47,111	5,235	1.00	1,745
HD - PAVE / 2	39,389	4,377	0.90	39,432	4,381	1.00	1,460
HD TOTAL:	86,489	9,610	1.97	86,543	9,616		3,205
			0.00				
HDSW / 1	7,455	828	0.17	7,523	836	0.50	139
HDSW / 2	9,436	1,048	0.22	9,514	1,057	0.50	176
HDSW / 3	3,528	392	0.08	3,568	396	0.50	66
HDSW TOTAL:	20,419	2,269	0.47	20,605	2,289		381
			0.00				
LD - PAVE / 1	16,792	1,866	0.38	16,825	1,869	0.67	418
LD - PAVE / 2	24,380	2,709	0.56	24,412	2,712	0.67	606
LD TOTAL:	41,172	4,575	0.94	41,237	4,582		1,024
			0.00				
PLAYCOURT / 1	5,050	561	0.12	5,072	564	0.50	94
PLAYCOURT / 2	7,936	882	0.18	7,967	885	0.50	148
PLAYCOURT TOTAL:	12,986	1,443	0.30	13,039	1,449		242
			0.00				
S/WSITE / 1	1,420	158	0.03	1,430	159	0.33	17
S/WSITE / 2	413	46	0.01	419	47	0.33	5
S/WSITE / 3	3,615	402	0.08	3,635	404	0.33	44
S/WSITE / 4	229	25	0.01	234	26	0.33	3
S/WSITE / 5	411	46	0.01	421	47	0.33	5
S/WSITE / 6	1,598	178	0.04	1,615	179	0.33	20
S/WSITE / 7	1,315	146	0.03	1,328	148	0.33	16
S/WSITE / 8	1,843	205	0.04	1,856	206	0.33	23

S/WSITE TOTAL:	10,844	1,205	0.25	10,938	1,215		133
SECTIONAL TOTAL	278,091	30,899	6.34	279,248	31,028		6,379

PREDICTED QUANTITIES AND CALCULATIONS ARE BASED UPON COMPUTER GENERATED SURFACE MODELS UTILIZING ALL AVAILABLE SUPPLIED INFORMATION ON THE PRINTED PLAN SHEETS AS WELL AS DATA CONVERTED FROM THE SOURCE DIGITAL FILES. EXTREME CARE HAS BEEN TAKEN TO INPUT THE SUPPLIED DATA ACCURATELY. NO FIELD VERIFICATION OF THE DATA HAS BEEN UNDERTAKEN BY SITE TECH SOLUTIONS.

NO SPECIFIC WARRANTEES ARE EXPRESSED OR IMPLIED